

THE PRESENT STATUS OF TUNNELLING ACTIVITIES IN JAPAN

JULY 1975

Prepared by

JAPAN TUNNELLING ASSOCIATION

Shinko Dai-ichi Bldg.

14-7 Shintomi 2-chome Chuo-ku

TOKYO 104, JAPAN

Tel: 03-553-6186

The Present Status of Tunnelling
Activities in Japan.

1. Tunnel Construction in Japan.

--- History, Present Status and Future Prospect. ---

1.1 The Outline of Geomorphology and Geology in Japan.	1
1.1.1 Geomorphology.	1
1.1.2 Geology.	3
1.2 Railway Tunnel.	13
1.2.1 Outline.	13
1.2.2 History.	14
1.2.3 Future Prospect.	20
1.3 Subway.	25
1.4 Highway.	49
1.5 Water Supply and Sewer.	61
1.5.1 Tunnel for Water Supply.	61
(1) Outline.	
(2) History.	
(3) Future Prospect.	
1.5.2 Tunnel for Sewer.	68
(1) Outline.	
(2) History.	
(3) Future Prospect.	

1.6	Other Underground Works.	- - - - -	75
1.6.1	Tunnel for Agriculture.	- - - - -	75
	(1) Introduction.		
	(2) Progress.		
	(3) Future Prospect.		
1.6.2	Subsurface Urbanization.	- - - - -	81
	(1) Subsurface Parking Lots.		
	(2) Subsurface Market Quarter.		
1.6.3	Hydro-Electric Development.	- - - - -	87
	(1) Underground Station.		
	(2) Underground Power Line.		
2.	Summaries of Major Constructions.		
2.1	Seikan Undersea Railway Tunnel.	- - - - -	93
2.1.1	Outline.	- - - - -	93
2.1.2	History of 25 Years of Surveys.	- - - - -	95
2.1.3	Outline of the Project and the Present Status.	- - - - -	97
2.1.4	Technical Features.	- - - - -	98
	1) Advance Boring.		
	2) Grouting.		
	3) Excavation.		
	4) Shot-creting.		
	5) Drainage and Ventilation.		

2.2	Subway Construction.	- - - - -	111
2.2.1	Outline.	- - - - -	111
2.2.2	Example in Tokyo. I	- - - - -	115
	- Construction of station excavated by roof shield. -		
2.2.3	Example in Tokyo. II	- - - - -	121
	-Large section shield in water bearing layer (Hakusan shield of Metropolitan Subway Line No. 6).-		
2.2.4	Example in Tokyo. III	- - - - -	129
	- Shield work of large section in soft soil and protection of existing building. -		
2.2.5	Example in Osaka.	- - - - -	134
	- Shield work of double truck section under a river bed. -		
2.2.6	Example in Nagoya.	- - - - -	140
	- Excavation in river bed with cofferdam. -		
2.3	Ena-San Highway Tunnel Project.	- - - - -	147
2.3.1	General.	- - - - -	147
2.3.2	Geological Condition and Tunnelling Method.-		151
2.3.3	Rock Loads on the Steel Arch Supports.	- - -	152
2.3.4	Properties of the Ground Water.	- - - - -	153
2.3.5	Excavation of the Ventilation Shafts.	- - -	154
2.3.6	Acknowledgments.	- - - - -	155

2.4	3-Undersea Tunnels of Kanmon straits. - - - - -	162
2.4.1	Outline. - - - - -	162
2.4.2	Kanmon Railway Tunnel (Narrow gauge line). -	165
	(1) Outline.	
	(2) Exploratory Drift.	
	(3) Tunnel for Down Train.	
	(4) Tunnel for Up Train.	
2.4.3	New-Kanmon Railway Tunnel Rapid Trunk Line. -	174
	(1) Outline.	
	(2) Design and Construction.	
	(3) Outline of Execution of Works.	
	a) Inlined Shaft.	
	b) Main Tunnel.	
	c) Undersea Section.	
2.4.4	Kanmon Vehicular Tunnel. - - - - -	184
2.5	Railway Tunnel Works on Rapid Trunk Line. - - - -	190
2.5.1	Tunnels on Tohoku Rapid Trunk Line. - - - - -	190
	(1) Outline.	
	(2) The Outlines of the Works on Major Tunnels.	
	a) Zao Tunnel.	
	b) Ichinoseki Tunnel.	
	c) Fukushima Tunnel.	
	(3) Advanced Technologies Applied to the Tunnel works on Tohoku Rapid Trunk Line.	

2.5.2	Tunnels on Jo-etsu Rapid Trunk Line (Shinkansen).	- - - - -	198
(1)	Outline.		
(2)	Brief Sketches of Major Tunnels.		
1)	Dai-Shimizu Tunnel (22.235 Km).		
2)	Nakayama Tunnel (14.350 Km).		
3)	Haruna Tunnel (14.350 Km).		
(3)	Technology Applied to Jo-etsu Rapid Trunk Line.		
2.6	Other Expressways Tunnel Projects.	- - - - -	211
2.6.1	Sasago Tunnel Project.	- - - - -	211
2.6.2	Kan-etsu Tunnel Project.	- - - - -	214
3.	Outline of Construction Method Adopted in Japan.		
3.1	Rock Tunnelling.	- - - - -	222
3.1.1	General.	- - - - -	222
3.1.2	Excavation Methods.	- - - - -	224
(1)	Bottom Drift Method.		
(2)	Side Drift Method.		
(3)	Upper-half Cut Method.		
(4)	Full-face Method.		
(5)	Other Methods.		
(6)	State of Application of the Various Excavation Methods.		

3.1.3	Construction Equipment etc. - - - - -	227
(1)	Drilling.	
(2)	Blasting.	
(3)	Mucking and Hauling.	
(4)	Concreting.	
(5)	Pilot Boring.	
(6)	Power Source for Construction.	
3.2	Tunnelling Methods through Unfavorable Geology. -	232
3.2.1	Unfavorable Geology Likely to Entail Difficult Operations and Fundamental Countermeasures. -	232
3.2.2	Selection of Excavation Method. - - - - -	233
(1)	Section Shape.	
(2)	Divisional Excavation of a Tunnel Face.	
(3)	Short Bench Cut Method.	
3.2.3	Supplementary treatment in difficult ground.-	234
3.2.4	Examples of Various Methods of Construction.-	236
3.3	Shield Tunnelling Methods. - - - - -	245
3.3.1	Outline. - - - - -	245
3.3.2	Shield Tunnelling Method. - - - - -	245
(1)	Hand Mine Shield.	
(2)	Semi-mechanized Shield.	
(3)	The Fully Mechanized Shield.	

(4)	Open Face Shield.	
(5)	Blind Shield.	
(6)	Laminated Face Shield.	
(7)	Shield Method under Compressed Air.	
(8)	Shield Partly Subject to Compressed Air.	
(9)	Pressed Muddy Water Shield.	
(10)	Pipe Jacking Method.	
3.3.3	Example of Shield and Segment.	- - - - - 251
3.4	Cut-and-Cover Tunnelling.	- - - - - 261
3.4.1	Special Problems of Cut-and-Cover Tunnelling in Japan.	- - - - - 261
3.4.2	Examples.	- - - - - 262
3.5	Submerged Tunnel Method	- - - - - 287
3.5.1	Outline.	- - - - - 287
3.5.2	Construction Examples.	- - - - - 288
3.5.3	Features of Submerged Tunnel Method.	- - - - 288
3.5.4	Construction Procedures and Its Methods.	- - 290
(1)	Fabrication of Tunnel Elements.	
(2)	Dredging of the Trench.	
(3)	Foundation.	
(4)	Sinking of the Elements.	
(5)	Joinning.	
(6)	Joint Structure.	
(7)	Backfill.	